

कार्यालय : मध्यप्रदेश राज्य सहकारी आवास संघ मर्यादित

सहकार-भवन, टी.टी. नगर, भोपाल

दूरभाष 0755-4200675, 4232120, 2779368 फ़ैक्स 0755-2779368

(E-mail : awassangh@gmail.com web: Http://www.mpawassangh.in)

क्रमांक / आसंघ / तक / 2023 / 1470

भोपाल, दिनांक 20-02-2023


ई-निविदा आमंत्रण संशोधन सूचना

रचना टावर्स, रचना नगर भोपाल में होरिजॉन्टल एवं वर्टिकल एक्सपेंशन ज्वाइंट्स के वाटर प्रूफिंग कार्य (नान एस. ओ.आर) प्रतिशत आधार पर आधारित निविदा क्रमांक 1398 दिनांक 07.02.23 जारी की गई है, उक्त निविदा के बी.ओ.क्यू. के सीरियल क्रमांक 1 एवं 2 को निम्नानुसार पढ़ा जावे।

1	For vertical expansion work: Cleaning of expansion joint cutting grooves, filling of breaker roads as per site condition in the grooves and then filling of polysuphide sealent as per site condition. Apply 1.8 mm tk. G.I. sheet with Expansion Provision over the treatment area of vertical expansion joint area
2	For horizontal work area: Cleaning of expansion joint cutting grooves, filling of breaker roads as per site condition in the grooves and then filling of polysuphide sealent as per site condition. Apply 1.8 mm tk. G.I. sheet with Expansion Provision over the treatment area of Horizontal expansion joint area. 200 mm x 200 mm Masonry work of bricks will be on both side of expansion joint in horizontal field for Protection of Treatment Work from soil being used in Planter area for flow of Soil & Water. 13 mm Plaster will be done on exterior sides of Masomary and applying of elastometric water proof coating over the plastered surface area.

उक्त निविदा में उक्तानुसार संशोधन करते हुये निविदा क्रय करने की अंतिम तिथि दिनांक 27.02.2023 सायं 5.00 बजे तक आमंत्रित की जाती है। शेष नियम एवं शर्तें यथावत् रहेंगे। निविदा का विस्तृत विवरण वेबसाईट <http://www.mptenders.gov.in> एवं mpawassangh.in पर देखा जा सकता है।

S. NO.	DEPARTMENTAL STAGE	BIDDER'S STAGE	CRITICAL		REMARKS
			DATE	TIME	
1	Publishing Date	-	09-02-23	11:00:00	
2	-	Document Sale Start	09-02-23	17:00:00	
3	Seek Clarification Start Date	-	NA	NA	
4	Seek Clarification End Date	-	NA	NA	
5	Pre Bid Meeting Date	-	NA	NA	
6	-	Bid Submission Start Date	09-02-23	17:00:00	
7	-	Bid Submission End Date	27-02-23	17:00:00	
8	Bid Opening Date (Mandatory & Technical)	-	01-03-23	11:00:00	
9	Bid Opening Date (Financial-Indicative Only)	-			



मुख्य अभियंता


ESTIMATE FOR WATERPROOFING OF HORIZONTAL & VERTICAL JOINTS
IN RACHNA TOWERS

S.NO.	Particulars	Area	Unit	Rate	Amount
1	For vertical expansion work: Cleaning of expansion joint cutting grooves, filling of breaker rods as per site condition in the grooves and then filling of polysuphide sealent as per site condition. Apply 1.8 mm tk. G.I. sheet with Expansion Provision over the treatment area of vertical expansion joint area	432	R.Mt.	1435	619920
2	For horizontal work area: Cleaning of expansion joint cutting grooves, filling of breaker rods as per site condition in the grooves and then filling of polysuphide sealent as per site condition. Apply 1.8 mm tk.G.I. sheet withExpansion Provision over the treatment area of Horizontal expansion joint area. 200 mm x 200 mm Masonary work of bricks will be on both side of expansion joint in horizontal field for Protection of Treatment Work from soil being used in Planter areafor flow of Soil & Water. 13 mm Plaster will be done on exterior sides of Masomary and applying of elastometric water proof coating over the plastered surface area.	618		1935	1195830
	TOTAL (Rs. Eighteen Lakhs Fifteen Thousands Seven Hundred & Fifty only)				1815750


Sub Engineer
Awat Sangh


Assistant Engineer
Awat Sangh


Executive Engineer
Awat Sangh


Chief Engineer
Awat Sangh