

# कार्यालय :- म0प्र0 राज्य सहकारी आवास संघ मर्यादित

सहकार भवन नार्थ टी.टी. नगर, भोपाल

(दूरभाष 0755-4200675, 4232120, फ़ैक्स 0755-2779368)

(E-mail: awassangh@gmail.com web: Http://www.mpawassangh.in)

क्रमांक / आ.संघ / तक. / 2021 / 507


भोपाल, दिनांक 02/09/21

## कोटेशन सूचना

1000 एमटी क्षमता गोदाम सह ग्रेडिंग प्लांट ग्राम सियापुरा तहसील देवास जिला देवास (म.प्र.) का मरम्मत/मेंटेनेंस कार्य, पंजीकृत ठेकेदार/फर्म के माध्यम से कराया जाना है। कार्य की लागत राशि रू0 58063/- है। उक्त कार्य हेतु, पंजीकृत ठेकेदार/फर्म से कोटेशन आमंत्रित किये जाते हैं। कोटेशन दिनांक 13.9.2021 समय 3.00 बजे तक आमंत्रित किये जाते हैं। कोटेशन अधोहस्ताक्षरकर्ता के कार्यालय में दिनांक 13.9.2021 समय 3.30 बजे तक उपस्थित कोटेशन प्रस्तुतकर्ताओं के समक्ष खोले जायेंगे। कार्य की विस्तृत जानकारी आवास संघ की वेबसाईट mpawassangh.in पर देखी जा सकती है।

### नियम एवं शर्तें :-


- 1- कार्य का कार्यादेश प्राप्त होने के उपरांत 30 दिवस के अंतर्गत कार्य करना होगा।
- 2- स्वीकृत दर अनुसार भुगतान किया जावेगा, जिस पर अन्य कोई शुल्क/चार्ज देय नहीं होगा।
- 3- कार्य उपरान्त देयक (दो प्रतियों) में कार्यालय में प्रस्तुत करें।
- 4- कार्य का एस्टीमेट संलग्न है।


  
मुख्य अभियंता


**Detail estimate for Repairing work 1000 M.T. Godown cum grading plant at Village Siya Dist. Dewas (M.P.)**

S.No.	SOR	Particular of Item	No.	L	B	THK	Quantity	Unit	Rate	Amount
1	15.6.3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	1	7.64	0.2	0.2	0.305	cum	487	149
2	6.4.2	Brick work with well burnt brick chimney in bulls patent kiln crushing strength not less than 25 kg. Per sq.cm. & water absorption not more than 20% in superstructure above plinth level and upto floor two level i/c curing complete.								
		Cement Mortar 1:6 (1 cement : 6 sand)	1	7.64	0.2	0.20	0.305	cum	5344	1630
3	13.1.2	12mm cement plaster of mix : 1:6 (1 cement : 6 sand)	1	7.64	0.2		1.528	sqm	110	168
4	13.3.2	20mm cement plaster of mix : 1:6 (1cement : 6sand)	1	7.64	0.2		1.528	sqm	156	238
5	10.15.1	Steel work in built-up tubular trusses including cutting hoisting and fixing in position and applying a priming coat of approved steel primer builded and bolted including washer etc complete. Hot finished welded type tube.	1				211.9	kg.	107.85	22853

6	12.15	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50mm 0.05%, total coated thickness with zinc coating 120 gsm as per IS:277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5X 55mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	1			37.50	sqm	652	24450
7	12.16.1	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm + 0.05 % total coated thickness, Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :							
		Ridges plain (500 - 600mm).	1			2	sqm	722	1444
	12.16.2	Flashings/ Aprons.( Upto 600 mm)	1			10.1	sqm	706	7131
		<b>Total</b>							<b>58063</b>

  
**Sub Engineer**  
 M.P. State Co-op. Housing Fed.  
 Bhopal

  
**Assistant Engineer**  
 M.P. State Co-op. Housing Fed.  
 Bhopal

  
**Executive Engineer**  
 M.P. State Co-op. Housing Fed  
 Bhopal