

कार्यालय :- म0प्र0 राज्य सहकारी आवास संघ मर्यादित

सहकार भवन नार्थ टी.टी. नगर, भोपाल

(दूरभाष 0755-4200675, 4232120, फ़ैक्स 0755-2779368)

(E-mail: awassangh@gmail.com web: Http://www.mpawassangh.in)

क्रमांक/आ.संघ/तक./2021/ 505

भोपाल, दिनांक 01-9-21

कोटेशन सूचना

ग्राम तिल्लीमाफी जिला सागर (म.प्र.) में निर्मित 1000 एमटी क्षमता गोदाम सह ग्रेडिंग प्लांट में ग्रेडिंग मशीन स्थापना का कार्य, म.प्र. लोक निर्माण विभाग में पंजीकृत ठेकेदार/फर्म से कराया जाना है। कार्य की लागत राशि रू0 90419/- है। उक्त कार्य हेतु, पंजीकृत ठेकेदार/फर्म से कोटेशन आमंत्रित किये जाते हैं। कोटेशन दिनांक 13/9/21 समय 3.00 बजे तक आमंत्रित किये जाते हैं। कोटेशन अधोहस्ताक्षरकर्ता के कार्यालय में दिनांक समय 3.30 बजे तक उपस्थित कोटेशन प्रस्तुतकर्ताओं के समक्ष खोले जायेंगे।

नियम एवं शर्तें :-


- 1- कार्य का कार्यादेश प्राप्त होने के उपरांत 30 दिवस के अंतर्गत कार्य करना होगा।
- 2- स्वीकृत दर अनुसार भुगतान किया जावेगा, जिस पर अन्य कोई शुल्क/चार्ज देय नहीं होगा।
- 3- कार्य उपरान्त देयक (दो प्रतियों) में कार्यालय में प्रस्तुत करें।
- 4- कार्य का एस्टीमेट संलग्न है।


मुख्य अभियंता


Detail Estimate for Construction of 1000 MT Capacity Godown cum grading plant at
Village TilliMafi Dist. Sagar (M.P.)

S.No.	SOR	Item	Unit	Qty.	Rate	Amount
1	15.3/ P-55	Item No. 1 Demolishing RCC work manually by mechanical means including taking of steel bars and disposal of vice able metal with on 50 meter lead up. as per direction of engineer in charge.	Cum	1.646	667	1097
2	15.2.2/	Item No. 2 Demolishing cement concrete manually by mechanical means 1:4:8 learner mix.	Cum	1.646	282	464
3	2.6.1	Item No.3 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in over areas foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm. on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m All kinds of soil.	cum	21.11	123	2596
4	4.1.2.2	Item No. 4 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 4.1.2 with 40mm nominal size graded stone aggregate. M 10 .	cum	1.153	3258	3756

5	6.3	Item No. 5 Brick work with well burn chimney bricks in pull patent trench kiln crushing strength not less than 25 kg. Per sq cm. and water absorption not more than 20 % in foundation in plinth c. m. 1:6	cum	3.322	2519	8368
6	13.1.1	Item No. 6 12 mm cement plaster of mix : 1:6 (1 cement : 6 sand)	Sqm	16.61	92	1528
7	4.2.1/ P-4	Item No. 7 Providing and laying cement concrete in retaining walls return walls any thickness including attached pilasters columns pillars posts struts buttresses string or lacing courses parapets coping bed blocks anchor blocks plain window sills fillets etc upto floor two level excluding the cost of centering shuttering any finishing with 20mm nominal size.	Cum	15.632	4645	72610
					Total	90419


Sub Engineer
Awass Sangh


Assistant / Executive Engineer
Awass Sangh


Chief Engineer
Awass Sangh